BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT37134

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/11/2019-20, Date: 11.07.2019

Improvements to Roads and Drains to Vinayakanagar Church road and surrounding area in Ward No 11 (Kuvempunagara) in Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SAMBASHIVA REDDY C ( )		
				In Figures		In Words
1	275.03	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	210.95	58017.58	Rupees Two Hundred Ten and Ninety Five Paise Only
2	877.5	Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	96.27	84476.93	Rupees Ninety Six and Twenty Seven Paise Only
3	87.75	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	641.83	56320.58	Rupees Six Hundred Forty One and Eighty Three Paise Only
4	520	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	847.21	440549.20	Rupees Eight Hundred Forty Seven and Twenty One Paise Only
5	3.6	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4678.02	16840.87	Rupees Four Thousand Six Hundred Seventy Eight and Two Paise Only
6	11.34	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5027.33	57009.92	Rupees Five Thousand Twenty Seven and Thirty Three Paise Only
7	21.6	Providing ruled pointing 20 mm deep to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	130.19	2812.10	Rupees One Hundred Thirty and Nineteen Paise Only
8	18	Providing precast slab of 250mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge	Sqm	4686.57	84358.26	Rupees Four Thousand Six Hundred Eighty Six and Fifty Seven
9	585	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge	Sqm	2021.5	1182577.50	Rupees Two Thousand Twenty One and Fifty
10	67.1	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4971.43	333582.95	Rupees Four Thousand Nine Hundred Seventy One and Forty Three Paise Only
					2316545.90	

C. Sambasheva Reddy
Signature of the Contractor

13/09
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

13/09